

**Submittal Data:12RLFF
Inverter Driven Heat Pump**

12,000 BTU Floor Mount

Job Name: _____

Date: _____

Location: _____

Approval: _____

Engineer: _____

Construction: _____

Submitted to: _____

Unit #: _____

Submitted by: _____

Drawing #: _____

Reference: _____

General Features

- Wired or wireless remote
- Apple catechin filter
- Ion deodorizing filter
- Sleep timer
- 24-hour timer
- Auto louver: up/down
- Auto mode
- Powerful mode
- Standard Warranty: 5 years parts, 7 years compressor. Applies to systems purchased before June 1st 2015*
- Extended Warranty: 10 years parts, 10 years compressor. Systems that have been installed on or after June 1st 2015 by licensed contractors and the online Product Registration has been submitted.**
- Elite Contractor Extended Warranty: 12 years parts, 12 years compressor. Systems that have been installed on or after June 1st 2015 by contractors who have met requirements and have been approved for elite contractor status plus, the online Product Registration has been submitted.***

Model Information

Condenser..... AOU12RLFF
Evaporator..... AGU12RLF

Electrical
Available Voltage Range..... 208/230V AC 1ph-60Hz
Minimum Circuit Ampacity..... 10.8 A
Max Fuse Size..... 15A
Max Starting Current..... 6.7 A

Input Power

Cooling..... 0.91 kW
Heating..... 1.44 kW

Running Current

Cooling..... 4.2 A
Heating..... 6.7 A

Capacity

Nominal Cooling..... 12,000 Btu/h
Min-Max Cooling..... 3,100 – 14,300 Btu/h
Nominal Heating..... 16,000 Btu/h
Min-Max Heating..... 3,100 – 19,500 Btu/h

Compressor

Motor Output..... 850 W
Refrigerant..... R410a
Charge..... 2 lbs. 10 oz.
Oil..... FREOL α68SZ

Fan Motor

(Condenser) Type: DC Propeller x 1
(Condenser) Motor Output..... 115 W
(Evaporator) Type: DC..... Cross flow fan x2
(Evaporator) Motor Output..... 16 W x2
Thermal Protection

Evaporator..... (on) 248 ± 27°F (120 ± 15°C) / (off) 302 ± 27°F (150 ± 15°C)
Condenser..... (on) 203 ± 18°F (95 ± 10°C) / (off) 212 ± 27°F (100 ± 15°C)

Heat Exchanger

Dimensions
(H x W x D) in.(mm)..... 23-1/8 x 34-11/16 x 1-7/16 (588x881x36.4)
Fin Pitch..... 20 FPI
Rows x Stages..... 2 x 28
Pipe Type (Material)..... Copper
Fin Type (Material)..... Aluminum

Note: Specifications are based on the following conditions.
Cooling: Indoor temperature of 80°F (26.7°C) DB/67°F (19.4°C) WB, and outdoor temperature of 95°F (35°C) DB/75°F (23.9°C) WB.
Heating: Indoor temperature of 70°F (21.1°C) DB/59°F (15°C) WB, and outdoor temperature of 47°F (8.3°C) DB/43°F (6.1°C) WB.
Pipe length: 24ft. 7in. (7.5m). Height difference: 0ft. (0in) (Outdoor unit – indoor unit) (*Standard warranty**10 year warranty***12 year warranty)



Operation Temperature Range

Cooling..... 14°F - 115°F (-10°C - 46°C)
Heating..... -5°F - 75°F (-21°C - 24°C)

Efficiency

SEER..... 22.7
EER (cooling)..... 3.87 kW/kW
COP (heating)..... 3.27 kW/kW
HSPF (heating)..... 11.6 Btu/hW

Enclosure (Condenser)

Material..... Painted galvanized steel
Color..... Beige (10 YR 7.5/1.0 NN)

Sound Pressure Level

Condenser..... 53 dB(A)
Evaporator..... 40 dB(A)

Dimensions

H x W x D
Condenser in. (mm)..... 24-7/16 x 31-1/8 x 11-7/16 (620x790x290)
Evaporator in. (mm)..... 23-5/8 x 29-1/8 x 7-7/8 (600x740x200)

Connection Pipe

Liquid..... 1/4"
Gas..... 3/8"
Method (Liquid/Gas)..... Brazing
Max Length (Pre-charge)..... 66ft. (20m) / (49 ft. {15m})
Max Height Difference..... 49 ft. (15m)

Weight

Condenser..... 84 lbs. (38 kg)
Evaporator..... 31 lbs. (14 kg)

Accessories

UTY-RNNUM..... Wired Remote Control
UTY-RVNUM..... Wired Remote Control (backlit, shows room temp.)
UTY-RSNUM..... Wired Remote Control (simple)
UTY-XWZXZ5..... Dry Contact Wire Kit

Intertek®ETL Number

AOU12RLFF..... 91986
AGU12RLF..... 91986



Fujitsu General America, Inc.
353 Route 46 West
Fairfield, NJ 07004
Toll Free: 1-888-888-3424
Fax: (973) 836-0447
www.fujitsugeneral.com

Dimensions:12RLFF

[Unit: in. (mm)]

